



Vineyard Mechanical Services

PO Box 773

West Tisbury, MA 02575

(508) 693-1298

info@vineyardmech.com

23 March 2023

Proposal submitted to:

Name: Town of Chilmark

Street:

City:

State: MA

Phone:

Work to be performed at:

Location: Chilmark Community Center

Job Phone:

Job Number: CH0123

Date of plans:

Designer:

We hereby propose to provide the materials, labor, and transportation necessary to perform the following service:

- Install a 4-zone heat pump/ air conditioning system as discussed and based on site visit
- The Main Hall will have (4) 24KBTU wall mounted units, 2 on the front wall and 2 on the back
- The outdoor units will be located on the back side of the building, locations TBD
- Unit lines will run on the exterior to the condenser location in a PVC jacket. The front (road side) unit lines will run on the exterior, and then pass thru the crawl space to the condenser location
- **Indoor units** Fujitsu ASU24RLF wall mounted cassettes
- **Condensers** Fujitsu AOU45RLXFZ multi zone heat pump inverter
- **Control** Fujitsu standard hand-held control, one for each unit

Notes: Electrical components as specified are provided, as well as coordination as needed with electrical contractor. Electrical labor is **NOT** included in contract price. All of the interconnecting lines will be on the exterior of the building. All unit locations will be verified before installation. Any additional carpentry as may be needed for access, chases, etc. is by others.

All material is guaranteed to be as specified, and the above work to be performed and completed in a substantial workmanlike manner Any alteration or deviation from the above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements are contingent upon strikes, accidents or delays beyond our control. Owner will carry fire, tornado, and casualty insurance on the work in progress, as well as our tools and equipment on site. Public liability insurance in the amount of \$2,000,000 will be taken out to cover the above work by Lowe Energy Design Inc/ Vineyard Mechanical Services

Payment schedule:

First payment: Deposit	\$8000.00
Second payment: Equipment on site	8000.00
Third Payment: system installed and pressurized, ready for electric	8000.00
Fourth Payment: substantial completion	3800.00
Total	\$27800.00

Service Charge and Collection Fee: Payments not paid within fifteen days of invoice date shall be subject to a 1.5% monthly service charge. Accounts not paid in full within fifteen days of project completion invoice shall be subject to a collection fee, in addition to the service charge as above, equal to eighteen percent (18%) of the outstanding balance or \$50.00, whichever is greater. If LED must initiate collection proceedings, the client/contractor shall be responsible for costs associated therewith, including attorney's fees.

Note: we may withdraw this proposal if not accepted within 15 days

Acceptance of proposal

The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Date:

Client signature: